

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT



<b>APPLICATION FOR PERMIT TO DRILL</b>						1. WELL NAME and NUMBER NBU 921-29B4CS							
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT NATURAL BUTTES							
4. TYPE OF WELL Gas Well <input checked="" type="checkbox"/> Coalbed Methane Well: NO <input type="checkbox"/>						5. UNIT or COMMUNITIZATION AGREEMENT NAME NATURAL BUTTES							
6. NAME OF OPERATOR KERR-MCGEE OIL & GAS ONSHORE, L.P.						7. OPERATOR PHONE 720 929-6100							
8. ADDRESS OF OPERATOR P.O. Box 173779, Denver, CO, 80217						9. OPERATOR E-MAIL Andy.Lytle@anadarko.com							
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) UTU 0581			11. MINERAL OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>							
13. NAME OF SURFACE OWNER (if box 12 = 'fee')						14. SURFACE OWNER PHONE (if box 12 = 'fee')							
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')							
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input checked="" type="checkbox"/> (Submit Commingling Application) NO <input type="checkbox"/>			19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>							
20. LOCATION OF WELL		FOOTAGES		QTR-QTR		SECTION		TOWNSHIP		RANGE		MERIDIAN	
LOCATION AT SURFACE		1619 FNL 2069 FEL		SWNE		29		9.0 S		21.0 E		S	
Top of Uppermost Producing Zone		1227 FNL 1809 FEL		NWNE		29		9.0 S		21.0 E		S	
At Total Depth		1227 FNL 1809 FEL		NWNE		29		9.0 S		21.0 E		S	
21. COUNTY UINTAH			22. DISTANCE TO NEAREST LEASE LINE (Feet) 1227			23. NUMBER OF ACRES IN DRILLING UNIT 2400							
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 399			26. PROPOSED DEPTH MD: 11217 TVD: 11173							
27. ELEVATION - GROUND LEVEL 4867			28. BOND NUMBER WYB000291			29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 43-8496							
<b>Hole, Casing, and Cement Information</b>													
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight			
Surf	11	8.625	0 - 2790	28.0	J-55 LT&C	0.2	Type V	180	1.15	15.8			
							Class G	270	1.15	15.8			
Prod	7.875	4.5	0 - 11217	11.6	HCP-110 LT&C	12.5	Premium Lite High Strength	340	3.38	12.0			
							50/50 Poz	1610	1.31	14.3			
<b>ATTACHMENTS</b>													
<b>VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES</b>													
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER						<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN							
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)						<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER							
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)						<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP							
NAME Joel Malefyt				TITLE Regulatory Analyst				PHONE 720 929-6828					
SIGNATURE				DATE 11/18/2014				EMAIL joel.malefyt@anadarko.com					
API NUMBER ASSIGNED 43047549630000													
<b>APPROVAL</b>													

**Received: November 28, 2014**

**Kerr-McGee Oil & Gas Onshore. L.P.****NBU 921-29B4CS**

Surface:	1619 FNL / 2069 FEL	SWNE
BHL:	1227 FNL / 1809 FEL	NWNE

Section 29 T9S R21E

Unitah County, Utah  
Mineral Lease: USA UTU 000581

**ONSHORE ORDER NO. 1****DRILLING PROGRAM**

**1. & 2.a** **Estimated Tops of Important Geologic Markers:**  
**Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:**

<u>Formation</u>	<u>Depth</u>	<u>Resource</u>
Uinta	0 - Surface	
Green River	1,572'	
Birds Nest	1,834'	Water
Mahogany	2,340'	Water
Wasatch	4,890'	Gas
Mesaverde	7,886'	Gas
Sego	10,123'	Gas
Castlegate	10,188'	Gas
Blackhawk	10,573'	Gas
TVD =	11,173'	
TD =	11,217'	

- 2.b** Kerr McGee Oil & Gas Onshore LP (Kerr McGee) may elect to drill to (i) the Blackhawk formation (part of the Mesaverde Group), (ii) to a shallower depth within the Mesaverde Group, or (iii) to the Wasatch Formation. If Kerr McGee drills to the Blackhawk formation, please refer to Blackhawk as the bottom formation. The attached Blackhawk Drilling Program includes Total Vertical Depth, Total Depth, and appropriate casing and cement programs for the deeper formation.

If Kerr-McGee drills to a shallower depth in the Mesaverde Group or to the Wasatch Formation, please refer to the attached Wasatch/Mesaverde Drilling Program which includes Total Vertical Depth, Total Depth, and appropriate casing and cement programs for the shallower formations.

**3.** **Pressure Control Equipment**

Please refer to the Standard Operating Practices on file with the BLM Vernal Field Office.

**4. Proposed Casing & Cementing Program:**

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program

**5. Drilling Fluids Program:**

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program

**6. Evaluation Program:**

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program

**7. Abnormal Conditions:****7.a Blackhawk (Part of Mesaverde Group)**

Maximum anticipated bottom hole pressure calculated at 11173' TVD, approximately equals  
7,151 psi (0.64 psi/ft = actual bottomhole gradient)

---

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 4,677 psi (bottom hole pressure  
minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

---

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-  
(0.22 psi/ft-partial evac gradient x TVD of next csg point))

**7.b Wasach Formation/Mesaverde Group**

Maximum anticipated bottom hole pressure calculated at 10123' TVD, approximately equals  
6,175 psi (0.61 psi/ft = actual bottomhole gradient)

---

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 3,975 psi (bottom hole pressure  
minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

---

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-  
(0.22 psi/ft-partial evac gradient x TVD of next csg point))

**8. Anticipated Starting Dates:**

Drilling is planned to commence immediately upon approval of this application.

**9. Variances:**

Please refer to the Standard Operating Practices on file with the BLM Vernal Field Office.

**10. Other Information:**

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program



**KERR-McGEE OIL & GAS ONSHORE LP**  
**Blackhawk Drilling Program**

COMPANY NAME	KERR-McGEE OIL & GAS ONSHORE LP				DATE	August 13, 2014	
WELL NAME	NBU 921-29B4CS				TD	11,173'	11,217' MD
FIELD	Natural Buttes	COUNTY	Uintah	STATE	Utah	FINISHED ELEVATION	4,867'
SURFACE LOCATION	SWNE	1619 FNL	2069 FEL	Sec 29	T 9S	R 21E	
	Latitude:	40.009812	Longitude:	-109.573509		NAD 83	
BTM HOLE LOCATION	NWNE	1227 FNL	1809 FEL	Sec 29	T 9S	R 21E	
	Latitude:	40.011788	Longitude:	-109.572587		NAD 83	
OBJECTIVE ZONE(S)	BLACKHAWK (Part of the Mesaverde Group)						
ADDITIONAL INFO	Regulatory Agencies: BLM (Minerals), BLM (Surface), UDOGM Tri-County Health Dept.						

GEOLOGICAL			MECHANICAL		
LOGS	FORMATION TOPS	DEPTH	HOLE SIZE	CASING SIZE	MUD WEIGHT
		40'		14"	
			↑ 12-1/4 ↓	↑ 8-5/8", 28#, IJ-55, LTC ↓	↑ Air mist ↓
<b>All water flows encountered while drilling will be reported to the appropriate agencies.</b>		200'	↑	↑	↑
			↑ 11.00' ↓	↑ 8-5/8", 28#, IJ-55, LTC ↓	↑ Air mist ↓
	<b>Green River @</b>	<b>1,572'</b>			
	<b>Top of Birds Nest @</b>	<b>1,834'</b>			
	<b>Mahogany @</b>	<b>2,340'</b>			
	<b>Preset f/ GL @</b> <b>2,790' TVD</b>				
Note: 11" surface hole will usually be drilled ±400' below the lost circulation zone (aka bird's nest). Drilled depth may be ±200' of the estimated set depth depending on the actual depth of the loss zone.					
<b>Mud logging program TBD</b> <b>Cased hole logging program from TD - surf csg</b>	<b>Wasatch @</b>	<b>4,890'</b>	↑ 7-7/8" ↓	↑ 4-1/2" 11.6# HCP-110 Ultra DQX/LTC csg ↓	↑ Water / Fresh Water Mud 8.3-12.5 ppg ↓
	<b>Mesaverde @</b>	<b>7,886' TVD</b>			
	<b>Sego @</b>	<b>10,123' TVD</b>			
	<b>Castlegate @</b>	<b>10,188' TVD</b>			
	<b>Blackhawk</b>	<b>10,573' TVD</b>			
<b>Max anticipated Mud required</b> <b>12.5 ppg</b>	<b>T.D. @</b>	<b>11,173' TVD</b> <b>11,217' MD</b>			





## KERR-McGEE OIL & GAS ONSHORE LP

### Blackhawk Drilling Program

**CASING PROGRAM**

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS			
						BURST	COLLAPSE	LTC	DQX
								TENSION	
CONDUCTOR	14"	0-40'							
						3,390	1,880	348,000	N/A
SURFACE	8-5/8"	0 to 2,790	28.00	IJ-55	LTC	1.93	1.44	5.09	N/A
						10,690	8,650	279,000	367,174
PRODUCTION	4-1/2"	0 to 5,000	11.60	HCP-110	DQX	1.19	1.19		3.49
	4-1/2"	5,000 to 11,217'	11.60	HCP-110	LTC	1.19	1.19	4.78	

**Surface Casing:**

(Burst Assumptions: TD = 12.5 ppg) 0.73 psi/ft = frac gradient @ surface shoe

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

**Production casing:**

(Burst Assumptions: Pressure test with 8.4ppg @ 9000 psi) 0.64 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

**CEMENT PROGRAM**

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80	1.15
Option 1			+ 0.25 pps flocele				
	TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80	1.15
			+ 2% CaCl + 0.25 pps flocele				
SURFACE		<b>NOTE: If well will circulate water to surface, option 2 will be utilized</b>					
Option 2	LEAD	2,290'	Premium cmt + 16% Gel + 10 pps gilsonite	280	35%	12.00	2.86
			+ 0.25 pps Flocele + 3% salt BWOC + GR 3 pps				
	TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80	1.15
			+ 0.25 pps flocele				
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80	1.15
PRODUCTION	LEAD	4,387'	Premium Lite II +0.25 pps celloflake + .4% FL-52	340	35%	12.00	3.38
			+ .3% R-3 + .5 lbs/sk Kol-Seal + 6%Bentonite II +				
			1.2% Sodium Metasilicate + .05 lbs/sk Static Free				
	TAIL	6,830'	50/50 Poz/G + 10% salt + .05 lbs/sk Static Free	1,610	35%	14.30	1.31
			+ 1.2% Sodium Metasilicate + .5 % EC-1				
			+ .002 gps FP-6L + 2% Bentonite II				

\*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

\*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

**FLOAT EQUIPMENT & CENTRALIZERS**

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. 15 centralizers for a Mesaverde and 20 for a Blackhawk well. 1 centralizer on the first 3 joints and one every third joint thereafter.

**ADDITIONAL INFORMATION**

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.

IF extreme mud losses are observed OR cement doesn't reach surface on a well on the pad, a DV Tool may be used. With Cement Baskets above and Below it.

**DRILLING ENGINEER:**

Matt Stiasny/Paul Wages

**DATE:****DRILLING SUPERINTENDENT:**

Lovel Young

**DATE:****Received: November 18, 2014**

[illegible]



## KERR-McGEE OIL & GAS ONSHORE LP

### Wasatch/Mesaverde Drilling Program

**CASING PROGRAM**

						DESIGN FACTORS			
						LTC		DQX	
	SIZE	INTERVAL		WT.	GR.	CPLG.	BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'							
							3,390	1,880	348,000
SURFACE	8-5/8"	0	to 2,790	28.00	IJ-55	LTC	1.93	1.44	5.09
							7,780	6,350	267,035
PRODUCTION	4-1/2"	0	to 5,000	11.60	I-80	DQX	1.11	1.01	2.77
							10,690	8,650	223,000
	4-1/2"	5,000	to 10,167'	11.60	HCP-110	LTC	1.53	1.37	4.56

**Surface Casing:**

(Burst Assumptions: TD = 12.0 ppg)

0.73 psi/ft = frac gradient @ surface shoe

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

**Production casing:**

(Burst Assumptions: Pressure test with 8.4ppg @ 7000 psi)

0.61 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

**CEMENT PROGRAM**

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80	1.15
Option 1			+ 0.25 pps flocele				
	TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80	1.15
			+ 2% CaCl + 0.25 pps flocele				
SURFACE			<b>NOTE: If well will circulate water to surface, option 2 will be utilized</b>				
Option 2	LEAD	2,290'	Premium cmt + 16% Gel + 10 pps gilsonite	280	35%	12.00	2.86
			+ 0.25 pps Flocele + 3% salt BWOC + GR 3 pps				
	TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80	1.15
			+ 0.25 pps Flocele + 3% salt BWOC + GR 3 pps				
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80	1.15
PRODUCTION	LEAD	4,387'	Premium Lite II + 0.25 pps celloflake + .4% FL-52	340	35%	12.00	3.38
			+ .3% R-3 + .5 lbs/sk Kol-Seal + 6%Bentonite II +				
			1.2% Sodium Metasilicate + .05 lbs/sk Static Free				
	TAIL	5,780'	50/50 Poz/G + 10% salt + .05 lbs/sk Static Free	1,370	35%	14.30	1.31
			+ 1.2% Sodium Metasilicate + .5 % EC-1				
			+ .002 gps FP-6L + 2% Bentonite II				

\*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

\*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

**FLOAT EQUIPMENT & CENTRALIZERS**

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. 15 centralizers for a Mesaverde and 20 for a Blackhawk well. 1 centralizer on the first 3 joints and one every third joint thereafter.

**ADDITIONAL INFORMATION**

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.

IF extreme mud losses are observed OR cement doesn't reach surface on a well on the pad, a DV Tool may be used. With Cement Baskets above and Below it.

**DRILLING ENGINEER:**


Matt Stiasny/Paul Wages

**DATE:****DRILLING SUPERINTENDENT:**

Lovel Young

**DATE:**

**T9S, R21E, S.L.B.&M.**



NOTES:

- ▲ = Section Corners Located
1. Well footages are measured at right angles to the Section Lines.  
G.L.O. distances are shown in feet or chains.
  2. 1 chain = 66 feet.
  3. The Bottom of hole bears N33°22'05"E 470.14'  
from the Surface Position.
  4. NAD 83 Latitude & Longitude are (CORS 96)(EPOCH:2002).
  5. Bearings and Distances are based upon a Local Cartesian Grid,  
oriented to Geodetic North at the North 1/4 Corner of Section 8,  
T10S, R22E, S.L.B.&M. The Grid having a mean project height of  
5300'. Lineal units used are U.S. Survey Foot.
  6. Basis of elevation is Tri-Sta "Two Water" located in Lot 4 of Section  
1, T10S, R21E, S.L.B.&M. The elevation of this Tri-Sta is shown on  
the Big Pack Mtn NE 7.5 Min. Quadrangle as being 5238'.

**Kerr-McGee Oil & Gas Onshore, LP**  
1099 18th Street - Denver, Colorado 80202


WELL PAD - NBU 921-29G

**NBU 921-29B4CS**  
**WELL PLAT**

1227' FNL, 1809' FEL (Bottom Hole)  
NW  $\frac{1}{4}$  NE  $\frac{1}{4}$  OF SECTION 29, T9S, R21E,  
S.L.B.&M., UINTAH COUNTY, UTAH.



**CONSULTING, LLC**  
2155 North Main Street  
Sheridan, WY 82801  
Phone 307-674-0609  
Fax 307-674-0182



## SURVEYOR'S CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

No. 6028691-5-16-14  
 JOHN R. LAUGH  
 PROFESSIONAL LAND SURVEYOR  
 REGISTRATION No. 6028691  
 STATE OF UTAH

## TIMBERLINE

(435) 789-1365

ENGINEERING & LAND SURVEYING, INC.  
209 NORTH 300 WEST - VERNAL, UTAH 84078


DATE SURVEYED: 4-3-14	SURVEYED BY: J.W.	SHEET NO:  <b>4</b>  4 OF 18
DATE DRAWN: 4-14-2014	DRAWN BY: D.A.	
SCALE: 1" = 1000'	Date Last Revised:	

Received: November 18, 2014

WELL NAME	SURFACE POSITION					BOTTOM HOLE				
	NAD83		NAD27		FOOTAGES	NAD83		NAD27		FOOTAGES
	LATITUDE	LONGITUDE	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	LATITUDE	LONGITUDE	
NBU 921-29H1BS	40°00'35.378"N 40.009827°N	109°34'24.254"W 109.573404°W	40°00'35.505"N 40.009862°N	109°34'21.772"W 109.572714°W	1614' FNL 2040' FEL	40°00'37.650"N 40.010458°N	109°34'04.358"W 109.567877°W	40°00'37.777"N 40.010493°N	109°34'01.877"W 109.567188°W	1388' FNL 490' FEL
NBU 921-29G1BS	40°00'35.360"N 40.009822°N	109°34'24.380"W 109.573439°W	40°00'35.487"N 40.009858°N	109°34'21.898"W 109.572750°W	1616' FNL 2050' FEL	40°00'35.976"N 40.009993°N	109°34'21.294"W 109.572582°W	40°00'36.103"N 40.010029°N	109°34'18.812"W 109.571892°W	1554' FNL 1809' FEL
NBU 921-29H1CS	40°00'35.342"N 40.009817°N	109°34'24.507"W 109.573474°W	40°00'35.469"N 40.009852°N	109°34'22.025"W 109.572785°W	1618' FNL 2059' FEL	40°00'34.419"N 40.009561°N	109°34'04.336"W 109.567871°W	40°00'34.546"N 40.009596°N	109°34'01.855"W 109.567182°W	1715' FNL 490' FEL
NBU 921-29B4CS	40°00'35.324"N 40.009812°N	109°34'24.633"W 109.573509°W	40°00'35.451"N 40.009848°N	109°34'22.151"W 109.572820°W	1619' FNL 2069' FEL	40°00'39.207"N 40.010891°N	109°34'21.317"W 109.572588°W	40°00'39.333"N 40.010926°N	109°34'18.835"W 109.571899°W	1227' FNL 1809' FEL
NBU 921-29H4BS	40°00'35.306"N 40.009807°N	109°34'24.759"W 109.573544°W	40°00'35.433"N 40.009842°N	109°34'22.277"W 109.572855°W	1621' FNL 2079' FEL	40°00'31.188"N 40.008663°N	109°34'04.326"W 109.567868°W	40°00'31.315"N 40.008699°N	109°34'01.845"W 109.567179°W	2042' FNL 491' FEL
NBU 921-29G1CS	40°00'35.288"N 40.009802°N	109°34'24.885"W 109.573579°W	40°00'35.415"N 40.009838°N	109°34'22.404"W 109.572890°W	1623' FNL 2089' FEL	40°00'32.745"N 40.009096°N	109°34'21.296"W 109.572582°W	40°00'32.872"N 40.009131°N	109°34'18.815"W 109.571893°W	1881' FNL 1811' FEL
NBU 356-29E	40°00'35.530"N 40.009869°N	109°34'23.180"W 109.573105°W	40°00'35.657"N 40.009905°N	109°34'20.698"W 109.572416°W	1599' FNL 1956' FEL					

RELATIVE COORDINATES - From Surface Position to Bottom Hole

WELL NAME	NORTH	EAST	WELL NAME	NORTH	EAST	WELL NAME	NORTH	EAST	WELL NAME	NORTH	EAST
NBU 921-29H1BS	228.1'	1548.8'	NBU 921-29G1BS	62.0'	240.3'	NBU 921-29H1CS	-95.3'	1569.8'	NBU 921-29B4CS	392.6'	258.6'
WELL NAME	NORTH	EAST	WELL NAME	NORTH	EAST						
NBU 921-29H4BS	-418.7'	1589.9'	NBU 921-29G1CS	-257.8'	279.0'						



Kerr-McGee Oil & Gas Onshore, LP  
1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 921-29G

WELL PAD INTERFERENCE PLAT  
WELLS - NBU 921-29H1BS, NBU 921-29G1BS,  
NBU 921-29H1CS, NBU 921-29B4CS,  
NBU 921-29H4BS & NBU 921-29G1CS  
LOCATED IN SECTION 29, T9S, R21E,  
S.L.B.&M., UTAH COUNTY, UTAH.



CONSULTING, LLC  
2155 North Main Street  
Sheridan, WY 82801  
Phone 307-674-0609  
Fax 307-674-0182

**TIMBERLINE**


(435) 789-1365

ENGINEERING & LAND SURVEYING, INC.  
209 NORTH 300 WEST - VERNAL, UTAH 84078

DATE SURVEYED: 4-3-14	SURVEYED BY: J.W.	SHEET NO:
DATE DRAWN: 4-14-14	DRAWN BY: D.A.	7
SCALE: 1" = 60'	Date Last Revised:	7 OF 18

Received: November 18, 2014





WELL PAD - NBU 921-29G DESIGN SUMMARY

EXISTING GRADE @ CENTER OF WELL PAD = 4869.0'  
FINISHED GRADE ELEVATION = 4867.3'  
CUT SLOPES = 1.5:1; EXCEPT AS NOTED  
FILL SLOPES = 1.5:1  
TOTAL WELL PAD AREA = 3.64 ACRES  
TOTAL DISTURBANCE AREA = 4.82 ACRES  
SHRINKAGE FACTOR = 1.10  
SWELL FACTOR = 1.00

Kerr-McGee Oil & Gas Onshore, LP  
1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 921-29G

WELL PAD - LOCATION LAYOUT  
NBU 921-29H1BS, NBU 921-29G1BS,  
NBU 921-29H1CS, NBU 921-29B4CS,  
NBU 921-29H4BS & NBU 921-29G1CS  
LOCATED IN SECTION 29, T9S, R21E,  
S.L.B.&M., UTAH COUNTY, UTAH



CONSULTING, LLC  
2155 North Main Street  
Sheridan, WY 82801  
Phone 307-674-0609  
Fax 307-674-0182

WELL PAD QUANTITIES


TOTAL CUT FOR WELL PAD = 12,716 C.Y.  
TOTAL FILL FOR WELL PAD = 9,959 C.Y.  
TOPSOIL @ 6" DEPTH = 1,960 C.Y.  
EXCESS MATERIAL = 2,757 C.Y.

RESERVE PIT QUANTITIES

TOTAL CUT FOR RESERVE PIT  
+/- 10,250 C.Y.  
RESERVE PIT CAPACITY (2' OF FREEBOARD)  
+/- 39,290 BARRELS


WELL PAD LEGEND

- EXISTING WELL LOCATION
- PROPOSED WELL LOCATION
- PROPOSED BOTTOM HOLE LOCATION
- EXISTING CONTOURS (2' INTERVAL)
- PROPOSED CONTOURS (2' INTERVAL)
- PPL - PROPOSED PIPELINE
- EPL - EXISTING PIPELINE



HORIZONTAL 0 30' 60' 1" = 60'  
2' CONTOURS

SCALE: 1"=60' DATE: 5/16/14 SHEET NO:  
REVISED: RAL 7/7/14 8 8 OF 18



WELL PAD - NBU 921-29G (CLOSED LOOP) DESIGN SUMMARY

EXISTING GRADE @ CENTER OF WELL PAD = 4869.0'  
FINISHED GRADE ELEVATION = 4867.3'  
CUT SLOPES = 1.5:1; EXCEPT AS NOTED  
FILL SLOPES = 1.5:1  
TOTAL WELL PAD AREA = 3.64 ACRES  
TOTAL DISTURBANCE AREA = 4.82 ACRES  
SHRINKAGE FACTOR = 1.10  
SWELL FACTOR = 1.00

Kerr-McGee Oil & Gas Onshore, LP  
1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 921-29G

WELL PAD - LOCATION LAYOUT  
NBU 921-29H1BS, NBU 921-29G1BS,  
NBU 921-29H1CS, NBU 921-29B4CS,  
NBU 921-29H4BS & NBU 921-29G1CS  
LOCATED IN SECTION 29, T9S, R21E,  
S.L.B.&M., UTAH COUNTY, UTAH



CONSULTING, LLC  
2155 North Main Street  
Sheridan, WY 82801  
Phone 307-674-0609  
Fax 307-674-0182

WELL PAD QUANTITIES

TOTAL CUT FOR WELL PAD = 12,716 C.Y.  
TOTAL FILL FOR WELL PAD = 9,959 C.Y.  
TOPSOIL @ 6" DEPTH = 1,960 C.Y.  
EXCESS MATERIAL = 2,757 C.Y.

COMPLETIONS PIT QUANTITIES

TOTAL CUT FOR COMPLETIONS PIT  
+/- 8,100 C.Y.  
COMPLETIONS PIT CAPACITY  
(2' OF FREEBOARD)  
+/- 30,780 BARRELS

WELL PAD LEGEND

- EXISTING WELL LOCATION
- PROPOSED WELL LOCATION
- PROPOSED BOTTOM HOLE LOCATION
- EXISTING CONTOURS (2' INTERVAL)
- PROPOSED CONTOURS (2' INTERVAL)
- PPL - PROPOSED PIPELINE
- EPL - EXISTING PIPELINE




HORIZONTAL 0 30' 60' 1" = 60'

2' CONTOURS


SCALE: 1"=60' DATE: 7/7/14 SHEET NO:

REVISED: 8B 8B OF 18

Received: November 18, 2014



**CROSS SECTION A-A'**



**CROSS SECTION B-B'**

**Kerr-McGee Oil & Gas Onshore, LP**  
1099 18th Street - Denver, Colorado 80202

**WELL PAD - NBU 921-29G**

**WELL PAD - CROSS SECTIONS**  
NBU 921-29H1BS, NBU 921-29G1BS,  
NBU 921-29H1CS, NBU 921-29B4CS,  
NBU 921-29H4BS & NBU 921-29G1CS  
LOCATED IN SECTION 29, T9S, R21E,  
S.L.B.&M., UTAH COUNTY, UTAH



**CONSULTING, LLC**  
2155 North Main Street  
Sheridan, WY 82801  
Phone 307-674-0609  
Fax 307-674-0182

**TIMBERLINE**

**ENGINEERING & LAND SURVEYING, INC.**  
209 NORTH 300 WEST - VERNAL, UTAH 84078

(435) 789-1365

**HORIZONTAL** 0 50' 100' 1" = 100'  
**VERTICAL** 0 10' 20' 1" = 20'

**SCALE:** 1"=100'

**DATE:** 5/16/14


**SHEET NO:**

**9**

9 OF 18

**Received: November 18, 2014**





- PLEASE NOTE:
1. LOCATIONS OF PROPOSED FACILITIES AND PROPOSED PIPELINES DISPLAYED WITHIN THE PAD AREA ARE FOR VISUALIZATION PURPOSES ONLY. ACTUAL LOCATIONS TO BE DETERMINED DURING CONSTRUCTION.
  2. ACTUAL RECLAMATION AREA TO BE DETERMINED DURING INTERIM RECLAMATION.

WELL PAD - NBU 921-29G RECLAMATION DESIGN SUMMARY

TOTAL DISTURBANCE AREA = 4.86 ACRES (INCLUDING EXISTING)  
RECLAMATION AREA = 3.59 ACRES  
TOTAL WELL PAD AREA AFTER RECLAMATION = 1.27 ACRES

Kerr-McGee Oil & Gas Onshore, LP  
1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 921-29G

WELL PAD - RECLAMATION LAYOUT  
NBU 921-29H1BS, NBU 921-29G1BS,  
NBU 921-29H1CS, NBU 921-29B4CS,  
NBU 921-29H4BS & NBU 921-29G1CS  
LOCATED IN SECTION 29, T9S, R21E,  
S.L.B.&M., UINTAH COUNTY, UTAH




CONSULTING, LLC  
2155 North Main Street  
Sheridan, WY 82801  
Phone 307-674-0609  
Fax 307-674-0182

**TIMBERLINE**  
ENGINEERING & LAND SURVEYING, INC.  
209 NORTH 300 WEST - VERNAL, UTAH 84078

(435) 789-1365

WELL PAD LEGEND

- EXISTING WELL LOCATION
- PROPOSED WELL LOCATION
- EXISTING CONTOURS (2' INTERVAL)
- PROPOSED CONTOURS (2' INTERVAL)
- PPL — PROPOSED PIPELINE
- EPL — EXISTING PIPELINE
- RECLAMATION AREA



HORIZONTAL 0 30' 60' 1" = 60'  
2' CONTOURS

SCALE: 1"=60' DATE: 5/16/14 SHEET NO:

REVISED: 10 10 OF 18






PHOTO VIEW: FROM CORNER PIT E TO LOCATION STAKE

CAMERA ANGLE: NORTHERLY




PHOTO VIEW: FROM BEGINNING OF EXISTING ROAD

CAMERA ANGLE: SOUTHEASTERLY

**Kerr-McGee Oil & Gas Onshore, LP**  
1099 18th Street - Denver, Colorado 80202

### WELL PAD - NBU 921-29G

#### LOCATION PHOTOS

NBU 921-29H1BS, NBU 921-29G1BS,  
NBU 921-29H1CS, NBU 921-29B4CS,  
NBU 921-29H4BS & NBU 921-29G1CS  
LOCATED IN SECTION 29, T9S, R21E,  
S.L.B.&M., UTAH COUNTY, UTAH.



**CONSULTING, LLC**  
2155 North Main Street  
Sheridan, WY 82801  
Phone 307-674-0609  
Fax 307-674-0182

**TIMBERLINE**


(435) 789-1365

ENGINEERING & LAND SURVEYING, INC.  
209 NORTH 300 WEST - VERNAL, UTAH 84078

DATE PHOTOS TAKEN: 4-3-14	PHOTOS TAKEN BY: J.W.	SHEET NO:  <b>11</b> 11 OF 18
DATE DRAWN: 4-14-2014	DRAWN BY: D.A.	
Date Last Revised:		

**Received: November 18, 2014**





### Legend

- Proposed Well Location
- Natural Buttes Unit Boundary
- Access Route - Proposed

Distance From Well Pad - NBU 921-29G To Unit Boundary: ±16,911ft

### WELL PAD - NBU 921-29G

**TOPO A**  
 NBU 921-29H1BS, NBU 921-29G1BS,  
 NBU 921-29H1CS, NBU 921-29B4CS,  
 NBU 921-29H4BS & NBU 921-29G1CS  
 LOCATED IN SECTION 29, T9S, R21E,  
 S.L.B.&M., UINTAH COUNTY, UTAH

**Kerr-McGee Oil &  
 Gas Onshore L.P.**

1099 18th Street  
 Denver, Colorado 80202



**CONSULTING, LLC**  
 2155 North Main Street  
 Sheridan, Wyoming 82801  
 Phone 307-674-0609  
 Fax 307-674-0182



SCALE: 1:100,000

NAD83 USP Central

SHEET NO:

DRAWN: TL

DATE: 16 May 2014

**12**


REVISED:

DATE:

12 OF 18

**Received: November 18, 2014**





### Legend

- |                   |                   |                          |                      |                             |         |
|-------------------|-------------------|--------------------------|----------------------|-----------------------------|---------|
| ● Well - Proposed | ■ Well Pad        | --- Road - Proposed      | — County Road        | ■ Bureau of Land Management | ■ State |
| ● Well - Existing | — Road - Existing | — Culvert/LWC - Proposed | ■ Indian Reservation | ■ Private                   |         |

Total Proposed Road Length: ±0ft

### WELL PAD - NBU 921-29G

#### TOPO B

NBU 921-29H1BS, NBU 921-29G1BS,  
NBU 921-29H1CS, NBU 921-29B4CS,  
NBU 921-29H4BS & NBU 921-29G1CS  
LOCATED IN SECTION 29, T9S, R21E,  
S.L.B.&M., UINTAH COUNTY, UTAH

### Kerr-McGee Oil & Gas Onshore L.P.

1099 18th Street  
Denver, Colorado 80202



#### CONSULTING, LLC

2155 North Main Street  
Sheridan, Wyoming 82801  
Phone 307-674-0609  
Fax 307-674-0182

SCALE: 1" = 2,000ft

DRAWN: TL

REVISED: TL

NAD83 USP Central

DATE: 16 May 2014

DATE: 7 July 2014


SHEET NO:

**13**

13 OF 18

**Received: November 18, 2014**





Well locations derived from Utah Division of Oil, Gas and Mining (UDOGM) (oilgas.ogm.utah.gov). The estimated distances from proposed bore locations to the nearest existing bore locations are based on UDOGM data.

Proposed Well	Nearest Well Bore	Footage
NBU 921-29H1BS	NBU 313-29E	±316ft
NBU 921-29G1BS	NBU 356-29E	±154ft
NBU 921-29H1CS	NBU 421-29E	±614ft
NBU 921-29B4CS	NBU 356-29E	±399ft
NBU 921-29H4BS	NBU 421-29E	±487ft
NBU 921-29G1CS	NBU 356-29E	±318ft

### Legend

- Well - Proposed
- Bottom Hole - Proposed
- Bottom Hole - Existing
- Well Path
- Well Pad
- Well - 1 Mile Radius
- ☀ Producing
- ☺ Spudded
- APD Approved
- ⊗ Preliminary Location
- ⊕ Deferred
- ✕ Cancelled
- ⊖ Temporarily Abandoned
- ☀ Active Injector
- ⊖ Location Abandoned
- ⊖ Shut-In
- ⊖ Plugged & Abandoned

### WELL PAD - NBU 921-29G

TOPO C  
NBU 921-29H1BS, NBU 921-29G1BS,  
NBU 921-29H1CS, NBU 921-29B4CS,  
NBU 921-29H4BS & NBU 921-29G1CS  
LOCATED IN SECTION 29, T9S, R21E,  
S.L.B.&M., UINTAH COUNTY, UTAH

**Kerr-McGee Oil &  
Gas Onshore L.P.**

1099 18th Street  
Denver, Colorado 80202



**CONSULTING, LLC**  
2155 North Main Street  
Sheridan, Wyoming 82801  
Phone 307-674-0609  
Fax 307-674-0182

SCALE: 1" = 2,000ft

DRAWN: TL

REVISED:

NAD83 USP Central

DATE: 7 July 2014

DATE:

SHEET NO:


**14**

14 OF 18

**Received: November 18, 2014**



K:\ANADARKO\2014\2014\_06\_NBU\_921-29\_FOCUS\GIS\Maps\_ABCDENBU\_921-29G\_NBU\_921-29G\_D.mxd 7/8/2014 3:44:32 PM



NBU 921-29H1BS  
NBU 921-29G1BS  
NBU 921-29H1CS  
NBU 921-29B4CS  
NBU 921-29H4BS  
NBU 921-29G1CS

Proposed Liquid Pipeline	Length
Buried 6" (Max.) (Separator to Edge of Pad)	±530ft
Buried 6" (Max.) (Edge of Pad to Proposed 6" (Max.) Liquid Pipeline ROW In Progress)	±1,040ft
<b>TOTAL PROPOSED BURIED LIQUID PIPELINE =</b>	<b>±1,570ft</b>

Proposed Gas Pipeline	Length
Buried 10" (Meter House to Edge of Pad)	±530ft
Buried 10" (Edge of Pad to Proposed 16" Gas Pipeline ROW In Progress)	±1,040ft
Surface 4" (Proposed Pipeline Re-Route)	±595ft
<b>TOTAL PROPOSED BURIED GAS PIPELINE =</b>	<b>±1,570ft</b>
<b>TOTAL PROPOSED SURFACE GAS PIPELINE =</b>	<b>±595ft</b>

### Legend

● Well - Proposed	- - - Gas Pipeline - Proposed	- - - Liquid Pipeline - Proposed	- - - Road - Proposed	■ Bureau of Land Management	■ State
● Well - Existing	- - - Gas Pipeline - To Be Upgraded	- - - Liquid Pipeline - Existing	- - - Road - Existing	■ Indian Reservation	■ Private
■ Well Pad	- - - Gas Pipeline - Existing				

### WELL PAD - NBU 921-29G

TOPO D  
NBU 921-29H1BS, NBU 921-29G1BS,  
NBU 921-29H1CS, NBU 921-29B4CS,  
NBU 921-29H4BS & NBU 921-29G1CS  
LOCATED IN SECTION 29, T9S, R21E,  
S.L.B.&M., UINTAH COUNTY, UTAH

**Kerr-McGee Oil &  
Gas Onshore L.P.**

1099 18th Street  
Denver, Colorado 80202



**CONSULTING, LLC**  
2155 North Main Street  
Sheridan, Wyoming 82801  
Phone 307-674-0609  
Fax 307-674-0182

SCALE: 1" = 2,000ft

DRAWN: TL

REVISED:

NAD83 USP Central

DATE: 7 July 2014

DATE:

SHEET NO:


**15**

15 OF 18

**Received: November 18, 2014**



K:\ANADARKO\2014\2014\_06\_NBU\_921-29\_FOCUS\GIS\Maps\_ABCDENBU 921-29G\NBU 921-29G\_D2.mxd/16/2014 8:35:46 AM




Proposed Liquid Pipeline		Length	Proposed Gas Pipeline		Length
Buried 6" (Max.) (Separator to Edge of Pad)		±530ft	Buried 10" (Meter House to Edge of Pad)		±530ft
Buried 6" (Max.) (Edge of Pad to Proposed 6" (Max.) Liquid Pipeline ROW In Progress)		±1,040ft	Buried 10" (Edge of Pad to Proposed 16" Gas Pipeline ROW In Progress)		±1,040ft
TOTAL PROPOSED BURIED LIQUID PIPELINE =		±1,570ft	Surface 4" (Proposed Pipeline Re-Route)		±595ft
			TOTAL PROPOSED BURIED GAS PIPELINE =		±1,570ft
			TOTAL PROPOSED SURFACE GAS PIPELINE =		±595ft

<b>Legend</b>					
● Well - Proposed	■ Well Pad - Proposed	- - - Gas Pipeline - Proposed	- - - Liquid Pipeline - Proposed	- - - Road - Proposed	■ Bureau of Land Management
● Well - Existing	■ Well Pad - Existing	- - - Gas Pipeline - To Be Upgraded	- - - Liquid Pipeline - Existing	- - - Road - Existing	■ Indian Reservation
		- - - Gas Pipeline - Existing			■ State
					■ Private

<b>WELL PAD - NBU 921-29G</b>  <b>TOPO D2 (PAD &amp; PIPELINE DETAIL)</b> NBU 921-29H1BS, NBU 921-29G1BS, NBU 921-29H1CS, NBU 921-29B4CS, NBU 921-29H4BS & NBU 921-29G1CS LOCATED IN SECTION 29, T9S, R21E, S.L.B.&M., UINTAH COUNTY, UTAH		<b>Kerr-McGee Oil &amp; Gas Onshore L.P.</b>  1099 18th Street Denver, Colorado 80202		 <b>CONSULTING, LLC</b> 2155 North Main Street Sheridan, Wyoming 82801 Phone 307-674-0609 Fax 307-674-0182	
SCALE: 1" = 500ft DRAWN: TL REVISED:		NAD83 USP Central DATE: 16 May 2014 DATE:		SHEET NO: <b>16</b> 16 OF 18	

Received: November 18, 2014





### Legend

- Well - Proposed
- Bottom Hole - Proposed
- Bottom Hole - Existing
- Well Path
- Well Pad
- Lease Boundary
- Gas Pipeline - Proposed
- Gas Pipeline - To Be Upgraded
- Gas Pipeline - Existing
- Liquid Pipeline - Proposed
- Liquid Pipeline - Existing
- Road - Proposed
- Road - Existing
- Bureau of Land Management
- Indian Reservation
- State
- Private

### WELL PAD - NBU 921-29G

TOPO E  
 NBU 921-29H1BS, NBU 921-29G1BS,  
 NBU 921-29H1CS, NBU 921-29B4CS,  
 NBU 921-29H4BS & NBU 921-29G1CS  
 LOCATED IN SECTION 29, T9S, R21E,  
 S.L.B.&M., UINTAH COUNTY, UTAH

**Kerr-McGee Oil &  
 Gas Onshore L.P.**

1099 18th Street  
 Denver, Colorado 80202



**CONSULTING, LLC**  
 2155 North Main Street  
 Sheridan, Wyoming 82801  
 Phone 307-674-0609  
 Fax 307-674-0182

SCALE: 1" = 2,000ft

DRAWN: TL

REVISED:

NAD83 USP Central

DATE: 7 July 2014

DATE:

SHEET NO:

**17**

17 OF 18


**Received: November 18, 2014**





**Kerr-McGee Oil & Gas Onshore, LP  
WELL PAD - NBU 921-29G  
WELLS – NBU 921-29H1BS, NBU 921-29G1BS,  
NBU 921-29H1CS, NBU 921-29B4CS  
NBU 921-29H4BS & NBU 921-29G1CS  
SECTION 29, T9S, R21E, S.L.B.&M.  
UINTAH COUNTY, UTAH**

From the intersection of U.S. Highway 40 and 500 East Street in Vernal, Utah, proceed in an easterly, then southerly direction along U.S. Highway 40 approximately 3.3 miles to the junction of State Highway 45. Exit right and proceed in a southerly direction along State Highway 45 approximately 20.2 miles to the junction of the Glen Bench Road (County B Road 3260). Exit right and proceed in a southwesterly direction along the Glen Bench Road approximately 17.7 miles to a Class D County Road to the southwest. Exit right and proceed in a southwesterly direction along the Class D County Road approximately 3.9 miles to a second Class D County Road to the northwest. Exit right and proceed in a northwesterly direction along the second Class D County Road approximately 0.6 miles to a service road to the east. Exit right and proceed in an easterly, then northerly direction along the service road approximately 0.3 miles to a service road to the east. Exit right and proceed in an easterly direction along the service road approximately 0.4 miles to the proposed well location.

Total distance from Vernal, Utah to the proposed well location is approximately 46.4 miles in a southerly direction.



WELL DETAILS: NBU 921-29B4CS						
GL 4867 & 4 @ 4871.00ft (ASSUMED)						
+N/-S 0.00	+E/-W 0.00	Northing 14532757.94	Easting 2040061.28	Latitude 40.0096480	Longitude -109.5728200	
DESIGN TARGET DETAILS						
Name	TVD	+N/-S	+E/-W	Northing	Easting	Latitude
SEGO	10123.00	465.45	257.94	14533227.46	2040311.73	40.0109260
PBHL	11173.00	465.45	257.94	14533227.46	2040311.73	40.0109260
- plan hits target center						
- plan hits target center						
						Longitude
						Shape
						Circle (Radius: 25.00)
						Circle (Radius: 100.00)



SECTION DETAILS									
MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSect	
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	
800.00	10.00	28.99	797.47	38.07	21.10	2.00	28.99	43.52	
3363.23	10.00	28.99	3321.75	427.38	236.84	0.00	0.00	488.62	
3863.23	0.00	0.00	3819.22	465.45	257.94	2.00	180.00	532.14	
11217.01	0.00	0.00	11173.00	465.45	257.94	0.00	0.00	532.14	PBHL_NBU 921-29B4CS
PROJECT DETAILS: UTAH - UTM (feet), NAD27, Zone 12N						FORMATION TOP DETAILS			
Geodetic System: Universal Transverse Mercator (US Survey Feet) Datum: NAD 1927 (NADCON CONUS) Ellipsoid: Clarke 1866 Zone: Zone 12N (114 W to 108 W) Location: SECTION 27 T9S R21E System Datum: Mean Sea Level						TVDPath	MDPath	Formation	
						1572.00	1586.48	GREEN RIVER	
						1834.00	1852.52	BIRDSNEST	
						2340.00	2366.33	MAHOGANY	
						4890.00	4934.01	WASATCH	
						7886.00	7930.01	MESAVERDE	
						10123.00	10167.01	SEGO	
						10188.00	10232.01	CASTLEGATE	
						10573.00	10617.01	BLACKHAWK	
CASING DETAILS									
TVD			MD		Name		Size		
2790.00			2823.27		8 5/8"		8.625		



Scientific Drilling

## **US ROCKIES REGION PLANNING**

UTAH - UTM (feet), NAD27, Zone 12N

NBU 921-29G PAD

NBU 921-29B4CS

OH

Plan: PLAN #1 PRELIMINARY

## **Standard Planning Report**

25 July, 2014



**Received:** November 18, 2014

<b>Database:</b>	EDM 5000.1 Single User Db	<b>Local Co-ordinate Reference:</b>	Well NBU 921-29B4CS
<b>Company:</b>	US ROCKIES REGION PLANNING	<b>TVD Reference:</b>	GL 4867 & 4 @ 4871.00ft (ASSUMED)
<b>Project:</b>	UTAH - UTM (feet), NAD27, Zone 12N	<b>MD Reference:</b>	GL 4867 & 4 @ 4871.00ft (ASSUMED)
<b>Site:</b>	NBU 921-29G PAD	<b>North Reference:</b>	True
<b>Well:</b>	NBU 921-29B4CS	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	OH		
<b>Design:</b>	PLAN #1 PRELIMINARY		

<b>Project</b>	UTAH - UTM (feet), NAD27, Zone 12N		
<b>Map System:</b>	Universal Transverse Mercator (US Survey Feet)	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	NAD 1927 (NADCON CONUS)		
<b>Map Zone:</b>	Zone 12N (114 W to 108 W)		

<b>Site</b>	NBU 921-29G PAD, SECTION 27 T9S R21E			
<b>Site Position:</b>		<b>Northing:</b>	14,532,757.94 usft	<b>Latitude:</b> 40.0096480
<b>From:</b>	Lat/Long	<b>Easting:</b>	2,040,061.27 usft	<b>Longitude:</b> -109.5728200
<b>Position Uncertainty:</b>	0.00 ft	<b>Slot Radius:</b>	13.200 in	<b>Grid Convergence:</b> 0.92 °

<b>Well</b>	NBU 921-29B4CS, 1619 FNL 2069 FEL			
<b>Well Position</b>	<b>+N/-S</b>	0.00 ft	<b>Northing:</b>	14,532,757.94 usft
	<b>+E/-W</b>	0.00 ft	<b>Easting:</b>	2,040,061.27 usft
<b>Position Uncertainty</b>		0.00 ft	<b>Wellhead Elevation:</b>	0.00 ft
			<b>Ground Level:</b>	4,867.00 ft

<b>Wellbore</b>	OH				
<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination (°)</b>	<b>Dip Angle (°)</b>	<b>Field Strength (nT)</b>
	BGGM2014	07/24/14	10.83	65.78	51,909

<b>Design</b>	PLAN #1 PRELIMINARY			
<b>Audit Notes:</b>				
<b>Version:</b>	<b>Phase:</b>	PLAN	<b>Tie On Depth:</b>	0.00
<b>Vertical Section:</b>	<b>Depth From (TVD) (ft)</b>	<b>+N/-S (ft)</b>	<b>+E/-W (ft)</b>	<b>Direction (°)</b>
	0.00	0.00	0.00	28.99

<b>Plan Sections</b>										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	
800.00	10.00	28.99	797.47	38.07	21.10	2.00	2.00	0.00	28.99	
3,363.23	10.00	28.99	3,321.75	427.38	236.84	0.00	0.00	0.00	0.00	
3,863.23	0.00	0.00	3,819.22	465.45	257.94	2.00	-2.00	0.00	180.00	
11,217.01	0.00	0.00	11,173.00	465.45	257.94	0.00	0.00	0.00	0.00	PBHL_NBU 921-29B4

<b>Database:</b>	EDM 5000.1 Single User Db	<b>Local Co-ordinate Reference:</b>	Well NBU 921-29B4CS
<b>Company:</b>	US ROCKIES REGION PLANNING	<b>TVD Reference:</b>	GL 4867 & 4 @ 4871.00ft (ASSUMED)
<b>Project:</b>	UTAH - UTM (feet), NAD27, Zone 12N	<b>MD Reference:</b>	GL 4867 & 4 @ 4871.00ft (ASSUMED)
<b>Site:</b>	NBU 921-29G PAD	<b>North Reference:</b>	True
<b>Well:</b>	NBU 921-29B4CS	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	OH		
<b>Design:</b>	PLAN #1 PRELIMINARY		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
<b>Start Build 2.00</b>									
400.00	2.00	28.99	399.98	1.53	0.85	1.75	2.00	2.00	0.00
500.00	4.00	28.99	499.84	6.10	3.38	6.98	2.00	2.00	0.00
600.00	6.00	28.99	599.45	13.73	7.61	15.69	2.00	2.00	0.00
700.00	8.00	28.99	698.70	24.39	13.51	27.88	2.00	2.00	0.00
800.00	10.00	28.99	797.47	38.07	21.10	43.52	2.00	2.00	0.00
<b>Start 2563.23 hold at 800.00 MD</b>									
900.00	10.00	28.99	895.95	53.26	29.51	60.89	0.00	0.00	0.00
1,000.00	10.00	28.99	994.43	68.44	37.93	78.25	0.00	0.00	0.00
1,100.00	10.00	28.99	1,092.91	83.63	46.35	95.62	0.00	0.00	0.00
1,200.00	10.00	28.99	1,191.39	98.82	54.76	112.98	0.00	0.00	0.00
1,300.00	10.00	28.99	1,289.87	114.01	63.18	130.35	0.00	0.00	0.00
1,400.00	10.00	28.99	1,388.35	129.20	71.60	147.71	0.00	0.00	0.00
1,500.00	10.00	28.99	1,486.83	144.39	80.02	165.08	0.00	0.00	0.00
1,586.48	10.00	28.99	1,572.00	157.52	87.29	180.09	0.00	0.00	0.00
<b>GREEN RIVER</b>									
1,600.00	10.00	28.99	1,585.31	159.58	88.43	182.44	0.00	0.00	0.00
1,700.00	10.00	28.99	1,683.79	174.76	96.85	199.81	0.00	0.00	0.00
1,800.00	10.00	28.99	1,782.27	189.95	105.27	217.17	0.00	0.00	0.00
1,852.52	10.00	28.99	1,834.00	197.93	109.69	226.29	0.00	0.00	0.00
<b>BIRDSNEST</b>									
1,900.00	10.00	28.99	1,880.75	205.14	113.68	234.54	0.00	0.00	0.00
2,000.00	10.00	28.99	1,979.23	220.33	122.10	251.90	0.00	0.00	0.00
2,100.00	10.00	28.99	2,077.72	235.52	130.52	269.27	0.00	0.00	0.00
2,200.00	10.00	28.99	2,176.20	250.71	138.93	286.63	0.00	0.00	0.00
2,300.00	10.00	28.99	2,274.68	265.90	147.35	303.99	0.00	0.00	0.00
2,366.33	10.00	28.99	2,340.00	275.97	152.94	315.51	0.00	0.00	0.00
<b>MAHOGANY</b>									
2,400.00	10.00	28.99	2,373.16	281.08	155.77	321.36	0.00	0.00	0.00
2,500.00	10.00	28.99	2,471.64	296.27	164.19	338.72	0.00	0.00	0.00
2,600.00	10.00	28.99	2,570.12	311.46	172.60	356.09	0.00	0.00	0.00
2,700.00	10.00	28.99	2,668.60	326.65	181.02	373.45	0.00	0.00	0.00
2,800.00	10.00	28.99	2,767.08	341.84	189.44	390.82	0.00	0.00	0.00
2,823.27	10.00	28.99	2,790.00	345.37	191.40	394.86	0.00	0.00	0.00
<b>8 5/8"</b>									
2,900.00	10.00	28.99	2,865.56	357.03	197.85	408.18	0.00	0.00	0.00
3,000.00	10.00	28.99	2,964.04	372.21	206.27	425.55	0.00	0.00	0.00
3,100.00	10.00	28.99	3,062.52	387.40	214.69	442.91	0.00	0.00	0.00
3,200.00	10.00	28.99	3,161.00	402.59	223.11	460.28	0.00	0.00	0.00
3,300.00	10.00	28.99	3,259.48	417.78	231.52	477.64	0.00	0.00	0.00
3,363.23	10.00	28.99	3,321.75	427.38	236.84	488.62	0.00	0.00	0.00
<b>Start Drop -2.00</b>									
3,400.00	9.26	28.99	3,358.01	432.77	239.83	494.78	2.00	-2.00	0.00
3,500.00	7.26	28.99	3,456.96	445.34	246.79	509.15	2.00	-2.00	0.00
3,600.00	5.26	28.99	3,556.36	454.88	252.08	520.06	2.00	-2.00	0.00
3,700.00	3.26	28.99	3,656.08	461.39	255.69	527.50	2.00	-2.00	0.00
3,800.00	1.26	28.99	3,755.99	464.84	257.60	531.45	2.00	-2.00	0.00
3,863.23	0.00	0.00	3,819.22	465.45	257.94	532.14	2.00	-2.00	0.00
<b>Start 7353.78 hold at 3863.23 MD</b>									

<b>Database:</b>	EDM 5000.1 Single User Db	<b>Local Co-ordinate Reference:</b>	Well NBU 921-29B4CS
<b>Company:</b>	US ROCKIES REGION PLANNING	<b>TVD Reference:</b>	GL 4867 & 4 @ 4871.00ft (ASSUMED)
<b>Project:</b>	UTAH - UTM (feet), NAD27, Zone 12N	<b>MD Reference:</b>	GL 4867 & 4 @ 4871.00ft (ASSUMED)
<b>Site:</b>	NBU 921-29G PAD	<b>North Reference:</b>	True
<b>Well:</b>	NBU 921-29B4CS	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	OH		
<b>Design:</b>	PLAN #1 PRELIMINARY		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
3,900.00	0.00	0.00	3,855.99	465.45	257.94	532.14	0.00	0.00	0.00
4,000.00	0.00	0.00	3,955.99	465.45	257.94	532.14	0.00	0.00	0.00
4,100.00	0.00	0.00	4,055.99	465.45	257.94	532.14	0.00	0.00	0.00
4,200.00	0.00	0.00	4,155.99	465.45	257.94	532.14	0.00	0.00	0.00
4,300.00	0.00	0.00	4,255.99	465.45	257.94	532.14	0.00	0.00	0.00
4,400.00	0.00	0.00	4,355.99	465.45	257.94	532.14	0.00	0.00	0.00
4,500.00	0.00	0.00	4,455.99	465.45	257.94	532.14	0.00	0.00	0.00
4,600.00	0.00	0.00	4,555.99	465.45	257.94	532.14	0.00	0.00	0.00
4,700.00	0.00	0.00	4,655.99	465.45	257.94	532.14	0.00	0.00	0.00
4,800.00	0.00	0.00	4,755.99	465.45	257.94	532.14	0.00	0.00	0.00
4,900.00	0.00	0.00	4,855.99	465.45	257.94	532.14	0.00	0.00	0.00
4,934.01	0.00	0.00	4,890.00	465.45	257.94	532.14	0.00	0.00	0.00
<b>WASATCH</b>									
5,000.00	0.00	0.00	4,955.99	465.45	257.94	532.14	0.00	0.00	0.00
5,100.00	0.00	0.00	5,055.99	465.45	257.94	532.14	0.00	0.00	0.00
5,200.00	0.00	0.00	5,155.99	465.45	257.94	532.14	0.00	0.00	0.00
5,300.00	0.00	0.00	5,255.99	465.45	257.94	532.14	0.00	0.00	0.00
5,400.00	0.00	0.00	5,355.99	465.45	257.94	532.14	0.00	0.00	0.00
5,500.00	0.00	0.00	5,455.99	465.45	257.94	532.14	0.00	0.00	0.00
5,600.00	0.00	0.00	5,555.99	465.45	257.94	532.14	0.00	0.00	0.00
5,700.00	0.00	0.00	5,655.99	465.45	257.94	532.14	0.00	0.00	0.00
5,800.00	0.00	0.00	5,755.99	465.45	257.94	532.14	0.00	0.00	0.00
5,900.00	0.00	0.00	5,855.99	465.45	257.94	532.14	0.00	0.00	0.00
6,000.00	0.00	0.00	5,955.99	465.45	257.94	532.14	0.00	0.00	0.00
6,100.00	0.00	0.00	6,055.99	465.45	257.94	532.14	0.00	0.00	0.00
6,200.00	0.00	0.00	6,155.99	465.45	257.94	532.14	0.00	0.00	0.00
6,300.00	0.00	0.00	6,255.99	465.45	257.94	532.14	0.00	0.00	0.00
6,400.00	0.00	0.00	6,355.99	465.45	257.94	532.14	0.00	0.00	0.00
6,500.00	0.00	0.00	6,455.99	465.45	257.94	532.14	0.00	0.00	0.00
6,600.00	0.00	0.00	6,555.99	465.45	257.94	532.14	0.00	0.00	0.00
6,700.00	0.00	0.00	6,655.99	465.45	257.94	532.14	0.00	0.00	0.00
6,800.00	0.00	0.00	6,755.99	465.45	257.94	532.14	0.00	0.00	0.00
6,900.00	0.00	0.00	6,855.99	465.45	257.94	532.14	0.00	0.00	0.00
7,000.00	0.00	0.00	6,955.99	465.45	257.94	532.14	0.00	0.00	0.00
7,100.00	0.00	0.00	7,055.99	465.45	257.94	532.14	0.00	0.00	0.00
7,200.00	0.00	0.00	7,155.99	465.45	257.94	532.14	0.00	0.00	0.00
7,300.00	0.00	0.00	7,255.99	465.45	257.94	532.14	0.00	0.00	0.00
7,400.00	0.00	0.00	7,355.99	465.45	257.94	532.14	0.00	0.00	0.00
7,500.00	0.00	0.00	7,455.99	465.45	257.94	532.14	0.00	0.00	0.00
7,600.00	0.00	0.00	7,555.99	465.45	257.94	532.14	0.00	0.00	0.00
7,700.00	0.00	0.00	7,655.99	465.45	257.94	532.14	0.00	0.00	0.00
7,800.00	0.00	0.00	7,755.99	465.45	257.94	532.14	0.00	0.00	0.00
7,900.00	0.00	0.00	7,855.99	465.45	257.94	532.14	0.00	0.00	0.00
7,930.01	0.00	0.00	7,886.00	465.45	257.94	532.14	0.00	0.00	0.00
<b>MESAVERDE</b>									
8,000.00	0.00	0.00	7,955.99	465.45	257.94	532.14	0.00	0.00	0.00
8,100.00	0.00	0.00	8,055.99	465.45	257.94	532.14	0.00	0.00	0.00
8,200.00	0.00	0.00	8,155.99	465.45	257.94	532.14	0.00	0.00	0.00
8,300.00	0.00	0.00	8,255.99	465.45	257.94	532.14	0.00	0.00	0.00
8,400.00	0.00	0.00	8,355.99	465.45	257.94	532.14	0.00	0.00	0.00
8,500.00	0.00	0.00	8,455.99	465.45	257.94	532.14	0.00	0.00	0.00
8,600.00	0.00	0.00	8,555.99	465.45	257.94	532.14	0.00	0.00	0.00
8,700.00	0.00	0.00	8,655.99	465.45	257.94	532.14	0.00	0.00	0.00
8,800.00	0.00	0.00	8,755.99	465.45	257.94	532.14	0.00	0.00	0.00

<b>Database:</b>	EDM 5000.1 Single User Db	<b>Local Co-ordinate Reference:</b>	Well NBU 921-29B4CS
<b>Company:</b>	US ROCKIES REGION PLANNING	<b>TVD Reference:</b>	GL 4867 & 4 @ 4871.00ft (ASSUMED)
<b>Project:</b>	UTAH - UTM (feet), NAD27, Zone 12N	<b>MD Reference:</b>	GL 4867 & 4 @ 4871.00ft (ASSUMED)
<b>Site:</b>	NBU 921-29G PAD	<b>North Reference:</b>	True
<b>Well:</b>	NBU 921-29B4CS	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	OH		
<b>Design:</b>	PLAN #1 PRELIMINARY		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
8,900.00	0.00	0.00	8,855.99	465.45	257.94	532.14	0.00	0.00	0.00
9,000.00	0.00	0.00	8,955.99	465.45	257.94	532.14	0.00	0.00	0.00
9,100.00	0.00	0.00	9,055.99	465.45	257.94	532.14	0.00	0.00	0.00
9,200.00	0.00	0.00	9,155.99	465.45	257.94	532.14	0.00	0.00	0.00
9,300.00	0.00	0.00	9,255.99	465.45	257.94	532.14	0.00	0.00	0.00
9,400.00	0.00	0.00	9,355.99	465.45	257.94	532.14	0.00	0.00	0.00
9,500.00	0.00	0.00	9,455.99	465.45	257.94	532.14	0.00	0.00	0.00
9,600.00	0.00	0.00	9,555.99	465.45	257.94	532.14	0.00	0.00	0.00
9,700.00	0.00	0.00	9,655.99	465.45	257.94	532.14	0.00	0.00	0.00
9,800.00	0.00	0.00	9,755.99	465.45	257.94	532.14	0.00	0.00	0.00
9,900.00	0.00	0.00	9,855.99	465.45	257.94	532.14	0.00	0.00	0.00
10,000.00	0.00	0.00	9,955.99	465.45	257.94	532.14	0.00	0.00	0.00
10,100.00	0.00	0.00	10,055.99	465.45	257.94	532.14	0.00	0.00	0.00
10,167.01	0.00	0.00	10,123.00	465.45	257.94	532.14	0.00	0.00	0.00
<b>SEGO - SEGO_NBU 921-29B4CS</b>									
10,200.00	0.00	0.00	10,155.99	465.45	257.94	532.14	0.00	0.00	0.00
10,232.01	0.00	0.00	10,188.00	465.45	257.94	532.14	0.00	0.00	0.00
<b>CASTLEGATE</b>									
10,300.00	0.00	0.00	10,255.99	465.45	257.94	532.14	0.00	0.00	0.00
10,400.00	0.00	0.00	10,355.99	465.45	257.94	532.14	0.00	0.00	0.00
10,500.00	0.00	0.00	10,455.99	465.45	257.94	532.14	0.00	0.00	0.00
10,600.00	0.00	0.00	10,555.99	465.45	257.94	532.14	0.00	0.00	0.00
10,617.01	0.00	0.00	10,573.00	465.45	257.94	532.14	0.00	0.00	0.00
<b>BLACKHAWK</b>									
10,700.00	0.00	0.00	10,655.99	465.45	257.94	532.14	0.00	0.00	0.00
10,800.00	0.00	0.00	10,755.99	465.45	257.94	532.14	0.00	0.00	0.00
10,900.00	0.00	0.00	10,855.99	465.45	257.94	532.14	0.00	0.00	0.00
11,000.00	0.00	0.00	10,955.99	465.45	257.94	532.14	0.00	0.00	0.00
11,100.00	0.00	0.00	11,055.99	465.45	257.94	532.14	0.00	0.00	0.00
11,200.00	0.00	0.00	11,155.99	465.45	257.94	532.14	0.00	0.00	0.00
11,217.01	0.00	0.00	11,173.00	465.45	257.94	532.14	0.00	0.00	0.00
<b>TD at 11217.01 - PBHL_NBU 921-29B4CS</b>									

Design Targets									
Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
- hit/miss target									
- Shape									
SEGO_NBU 921-29B4C	0.00	0.00	10,123.00	465.45	257.94	14,533,227.47	2,040,311.72	40.0109260	-109.5718990
- plan hits target center									
- Circle (radius 25.00)									
PBHL_NBU 921-29B4C	0.00	0.00	11,173.00	465.45	257.94	14,533,227.47	2,040,311.72	40.0109260	-109.5718990
- plan hits target center									
- Circle (radius 100.00)									


Casing Points					
Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (in)	Hole Diameter (in)	
2,823.27	2,790.00	8 5/8"	8.625	11.000	

<b>Database:</b>	EDM 5000.1 Single User Db	<b>Local Co-ordinate Reference:</b>	Well NBU 921-29B4CS
<b>Company:</b>	US ROCKIES REGION PLANNING	<b>TVD Reference:</b>	GL 4867 & 4 @ 4871.00ft (ASSUMED)
<b>Project:</b>	UTAH - UTM (feet), NAD27, Zone 12N	<b>MD Reference:</b>	GL 4867 & 4 @ 4871.00ft (ASSUMED)
<b>Site:</b>	NBU 921-29G PAD	<b>North Reference:</b>	True
<b>Well:</b>	NBU 921-29B4CS	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	OH		
<b>Design:</b>	PLAN #1 PRELIMINARY		

Formations					
Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)
1,586.48	1,572.00	GREEN RIVER			
1,852.52	1,834.00	BIRDSNEST			
2,366.33	2,340.00	MAHOGANY			
4,934.01	4,890.00	WASATCH			
7,930.01	7,886.00	MESAVERDE			
10,167.01	10,123.00	SEGO			
10,232.01	10,188.00	CASTLEGATE			
10,617.01	10,573.00	BLACKHAWK			

Plan Annotations				
Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment
		+N/-S (ft)	+E/-W (ft)	
300.00	300.00	0.00	0.00	Start Build 2.00
800.00	797.47	38.07	21.10	Start 2563.23 hold at 800.00 MD
3,363.23	3,321.75	427.38	236.84	Start Drop -2.00
3,863.23	3,819.22	465.45	257.94	Start 7353.78 hold at 3863.23 MD
11,217.01	11,173.00	465.45	257.94	TD at 11217.01





**API Number: 4304754963**



**Well Name: NBU 921-29B4CS**

Township: T09.0S Range: R21.0E Section: 29 Meridian: S

Operator: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Map Prepared: 11/20/2014  
Map Produced by Diana Mason

Wells Query		Units	
Status		STATUS	
APD - Approved Permit		ACTIVE	
DRL - Spudded (Drilling Commenced)		EXPLORATORY	
GRW - Gas Injection		GAS STORAGE	
GS - Gas Storage		NF PP OIL	
LOC - New Location		NF SECONDARY	
OPS - Operation Suspended		PI OIL	
PA - Plugged Abandoned		PP GAS	
PGW - Producing Gas Well		PP GEOTHERMAL	
POW - Producing Oil Well		PP OIL	
SQW - Shut-in Gas Well		SECONDARY	
SOW - Shut-in Oil Well		TERMINATED	
TA - Temp. Abandoned			
TW - Test Well			
WOW - Water Disposal			
WW - Water Injection Well			
WSW - Water Supply Well			



**Received: November 20, 2014**

# United States Department of the Interior

## BUREAU OF LAND MANAGEMENT

Utah State Office  
440 West 200 South, Suite 500  
Salt Lake City, UT 84101

IN REPLY REFER TO:

3160

(UT-922)

November 25, 2014

Memorandum

To: Assistant Field Office Manager Minerals,  
Vernal Field Office

From: Michael Coulthard, Petroleum Engineer

Subject: 2014 Plan of Development Natural Buttes Unit  
Uintah County, Utah.

Pursuant to email between Diana Mason, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2014 within the Natural Buttes Unit, Uintah County, Utah.

API #	WELL NAME	LOCATION
(Proposed PZ WASATCH-MESA VERDE)		
<b>PAD NBU 921-29C</b>		
43-047-54931	NBU 921-29D1CS	Sec 29 T09S R21E 0708 FNL 2535 FWL
	BHL	Sec 29 T09S R21E 0537 FNL 0821 FWL
43-047-54932	NBU 921-29D1BS	Sec 29 T09S R21E 0700 FNL 2541 FWL
	BHL	Sec 29 T09S R21E 0167 FNL 0739 FWL
43-047-54933	NBU 921-29C4CS	Sec 29 T09S R21E 0724 FNL 2523 FWL
	BHL	Sec 29 T09S R21E 1062 FNL 2136 FWL
43-047-54934	NBU 921-29C4BS	Sec 29 T09S R21E 0716 FNL 2529 FWL
	BHL	Sec 29 T09S R21E 0735 FNL 2135 FWL
43-047-54935	NBU 921-29C1CS	Sec 29 T09S R21E 0692 FNL 2547 FWL
	BHL	Sec 29 T09S R21E 0408 FNL 2134 FWL
43-047-54936	NBU 921-29C1BS	Sec 29 T09S R21E 0684 FNL 2553 FWL
	BHL	Sec 29 T09S R21E 0067 FNL 2031 FWL
<b>PAD NBU 921-29B</b>		
43-047-54939	NBU 921-29B4BS	Sec 29 T09S R21E 0448 FNL 2118 FEL
	BHL	Sec 29 T09S R21E 0900 FNL 1807 FEL
43-047-54940	NBU 921-29B1CS	Sec 29 T09S R21E 0446 FNL 2109 FEL
	BHL	Sec 29 T09S R21E 0573 FNL 1806 FEL
43-047-54941	NBU 921-29B1BS	Sec 29 T09S R21E 0449 FNL 2128 FEL
	BHL	Sec 29 T09S R21E 0217 FNL 1878 FEL
43-047-54942	NBU 921-29A4CS	Sec 29 T09S R21E 0445 FNL 2099 FEL
	BHL	Sec 29 T09S R21E 1061 FNL 0490 FEL
43-047-54943	NBU 921-29A4BS	Sec 29 T09S R21E 0444 FNL 2089 FEL
	BHL	Sec 29 T09S R21E 0734 FNL 0490 FEL

Received: November 28, 2014



API #	WELL NAME	LOCATION
(Proposed PZ WASATCH-MESA VERDE)		
<b>PAD NBU 921-29B</b>		
43-047-54944	NBU 921-29A1CS	Sec 29 T09S R21E 0441 FNL 2069 FEL
	BHL	Sec 29 T09S R21E 0408 FNL 0489 FEL
43-047-54945	NBU 921-29A1BS	Sec 29 T09S R21E 0442 FNL 2079 FEL
	BHL	Sec 29 T09S R21E 0034 FNL 0619 FEL
<b>PAD NBU 921-29E</b>		
43-047-54946	NBU 921-29D4BS	Sec 29 T09S R21E 2010 FNL 0734 FWL
	BHL	Sec 29 T09S R21E 0901 FNL 0818 FWL
43-047-54947	NBU 921-29D4CS	Sec 29 T09S R21E 2005 FNL 0742 FWL
	BHL	Sec 29 T09S R21E 1228 FNL 0819 FWL
43-047-54949	NBU 921-29E1BS	Sec 29 T09S R21E 2000 FNL 0751 FWL
	BHL	Sec 29 T09S R21E 1556 FNL 0820 FWL
43-047-54950	NBU 921-29E1CS	Sec 29 T09S R21E 1985 FNL 0777 FWL
	BHL	Sec 29 T09S R21E 1883 FNL 0820 FWL
43-047-54954	NBU 921-29E4BS	Sec 29 T09S R21E 1990 FNL 0768 FWL
	BHL	Sec 29 T09S R21E 2210 FNL 0820 FWL
43-047-54956	NBU 921-29E4CS	Sec 29 T09S R21E 1995 FNL 0760 FWL
	BHL	Sec 29 T09S R21E 2538 FNL 0821 FWL
<b>PAD NBU 921-29F</b>		
43-047-54948	NBU 921-29F1CS	Sec 29 T09S R21E 1980 FNL 1990 FWL
	BHL	Sec 29 T09S R21E 1717 FNL 2139 FWL
43-047-54951	NBU 921-29K1BS	Sec 29 T09S R21E 1982 FNL 1960 FWL
	BHL	Sec 29 T09S R21E 2537 FSL 2142 FWL
43-047-54952	NBU921-29F1BS	Sec 29 T09S R21E 1981 FNL 1980 FWL
	BHL	Sec 29 T09S R21E 1390 FNL 2137 FWL
43-047-54953	NBU 921-29F4CS	Sec 29 T09S R21E 1982 FNL 1970 FWL
	BHL	Sec 29 T09S R21E 2371 FNL 2141 FWL
43-047-54955	NBU 921-29F4BS	Sec 29 T09S R21E 1980 FNL 2000 FWL
	BHL	Sec 29 T09S R21E 2044 FNL 2140 FWL
<b>PAD NBU 921-29J</b>		
43-047-54957	NBU 921-29J4BS	Sec 29 T09S R21E 1689 FSL 1850 FEL
	BHL	Sec 29 T09S R21E 1717 FSL 1816 FEL
43-047-54958	NBU 921-29J1CS	Sec 29 T09S R21E 1681 FSL 1856 FEL
	BHL	Sec 29 T09S R21E 2044 FSL 1815 FEL
43-047-54959	NBU 921-29J1BS	Sec 29 T09S R21E 1674 FSL 1863 FEL
	BHL	Sec 29 T09S R21E 2371 FSL 1814 FEL
43-047-54960	NBU 921-29G4CS	Sec 29 T09S R21E 1666 FSL 1870 FEL
	BHL	Sec 29 T09S R21E 2535 FNL 1813 FEL
<b>PAD NBU 921-29I</b>		
43-047-54961	NBU 921-29P1CS	Sec 29 T09S R21E 1848 FSL 0907 FEL
	BHL	Sec 29 T09S R21E 0998 FSL 0468 FEL
43-047-54962	NBU 921-29P1BS	Sec 29 T09S R21E 1850 FSL 0897 FEL
	BHL	Sec 29 T09S R21E 1291 FSL 0495 FEL
43-047-54969	NBU 921-29H4CS	Sec 29 T09S R21E 1854 FSL 0877 FEL
	BHL	Sec 29 T09S R21E 2369 FNL 0491 FEL
43-047-54970	NBU 921-29I1BS	Sec 29 T09S R21E 1856 FSL 0868 FEL
	BHL	Sec 29 T09S R21E 2535 FSL 0491 FEL
43-047-54971	NBU 921-29I1CS	Sec 29 T09S R21E 1858 FSL 0858 FEL
	BHL	Sec 29 T09S R21E 2244 FSL 0483 FEL

API #	WELL NAME	LOCATION
(Proposed PZ WASATCH-MESA VERDE)		
<b>PAD NBU 921-29I</b>		
43-047-54972	NBU 921-29I4BS	Sec 29 T09S R21E 1860 FSL 0848 FEL BHL Sec 29 T09S R21E 1920 FSL 0494 FEL
43-047-54973	NBU 921-29I4CS	Sec 29 T09S R21E 1852 FSL 0887 FEL BHL Sec 29 T09S R21E 1618 FSL 0489 FEL
<b>PAD NBU 921-29G</b>		
43-047-54963	NBU 921-29B4CS	Sec 29 T09S R21E 1619 FNL 2069 FEL BHL Sec 29 T09S R21E 1227 FNL 1809 FEL
43-047-54964	NBU 921-29G1BS	Sec 29 T09S R21E 1616 FNL 2050 FEL BHL Sec 29 T09S R21E 1554 FNL 1809 FEL
43-047-54965	NBU 921-29G1CS	Sec 29 T09S R21E 1623 FNL 2089 FEL BHL Sec 29 T09S R21E 1881 FNL 1811 FEL
43-047-54966	NBU 921-29H1BS	Sec 29 T09S R21E 1614 FNL 2040 FEL BHL Sec 29 T09S R21E 1388 FNL 0490 FEL
43-047-54967	NBU 921-29H1CS	Sec 29 T09S R21E 1618 FNL 2059 FEL BHL Sec 29 T09S R21E 1715 FNL 0490 FEL
43-047-54968	NBU 921-29H4BS	Sec 29 T09S R21E 1621 FNL 2079 FEL BHL Sec 29 T09S R21E 2042 FNL 0491 FEL
<b>PAD NBU 921-29K</b>		
43-047-54974	NBU 921-29O1BS	Sec 29 T09S R21E 1862 FSL 2432 FWL BHL Sec 29 T09S R21E 1063 FSL 1818 FEL
43-047-54975	NBU921-29K4CS	Sec 29 T09S R21E 1856 FSL 2413 FWL BHL Sec 29 T09S R21E 1598 FSL 2145 FWL
43-047-54976	NBU 921-29K1CS	Sec 29 T09S R21E 1859 FSL 2422 FWL BHL Sec 29 T09S R21E 2210 FSL 2143 FWL
43-047-54977	NBU 921-29J4CS	Sec 29 T09S R21E 1869 FSL 2450 FWL BHL Sec 29 T09S R21E 1390 FSL 1817 FEL
43-047-54978	NBU 921-29G4BS	Sec 29 T09S R21E 1865 FSL 2441 FWL BHL Sec 29 T09S R21E 2208 FNL 1811 FEL
<b>PAD NBU 921-29L</b>		
43-047-54979	NBU 921-29L1BS	Sec 29 T09S R21E 1643 FSL 0551 FWL BHL Sec 29 T09S R21E 2374 FSL 0821 FWL
43-047-54980	NBU 921-29L1CS	Sec 29 T09S R21E 1641 FSL 0561 FWL BHL Sec 29 T09S R21E 2046 FSL 0822 FWL
43-047-54981	NBU 921-29L4BS	Sec 29 T09S R21E 1639 FSL 0571 FWL BHL Sec 29 T09S R21E 1719 FSL 0822 FWL
43-047-54982	NBU 921-29M1BS	Sec 29 T09S R21E 1636 FSL 0581 FWL BHL Sec 29 T09S R21E 1064 FSL 0823 FWL
<b>PAD NBU 921-30A</b>		
43-047-54986	NBU 921-30H1CS	Sec 30 T09S R21E 0865 FNL 0646 FEL BHL Sec 30 T09S R21E 1649 FNL 0536 FEL
43-047-54987	NBU 921-30H1BS	Sec 30 T09S R21E 0874 FNL 0643 FEL BHL Sec 30 T09S R21E 1267 FNL 0535 FEL
43-047-54988	NBU 92130B1CS	Sec 30 T09S R21E 0856 FNL 0651 FEL BHL Sec 30 T09S R21E 0572 FNL 1954 FEL
43-047-54989	NBU 921-30B1BS	Sec 30 T09S R21E 0846 FNL 0654 FEL BHL Sec 30 T09S R21E 0231 FNL 1954 FEL

API #	WELL NAME	LOCATION
(Proposed PZ WASATCH-MESA VERDE)		
<b>PAD NBU 921-30A</b>		
43-047-54990	NBU 921-30A1CS	Sec 30 T09S R21E 0837 FNL 0658 FEL
	BHL	Sec 30 T09S R21E 0524 FNL 0540 FEL
43-047-54991	NBU 921-30A1BS	Sec 30 T09S R21E 0828 FNL 0662 FEL
	BHL	Sec 30 T09S R21E 0194 FNL 0560 FEL
<b>PAD NBU 921-290</b>		
43-047-54992	NBU 921-29P4BS	Sec 29 T09S R21E 0496 FSL 1679 FEL
	BHL	Sec 29 T09S R21E 0337 FSL 0485 FEL
43-047-54993	NBU 921-29O4CS	Sec 29 T09S R21E 0493 FSL 1689 FEL
	BHL	Sec 29 T09S R21E 0120 FSL 1842 FEL
43-047-54994	NBU 921-29O4BS	Sec 29 T09S R21E 0486 FSL 1708 FEL
	BHL	Sec 29 T09S R21E 0409 FSL 1820 FEL
43-047-54995	NBU 921-29O1CS	Sec 29 T09S R21E 0489 FSL 1698 FEL
	BHL	Sec 29 T09S R21E 0736 FSL 1819 FEL
<b>PAD NBU 921-29N</b>		
43-047-54996	NBU 921-29N4CS	Sec 29 T09S R21E 0623 FSL 1903 FWL
	BHL	Sec 29 T09S R21E 0104 FSL 2111 FWL
43-047-54997	NBU 921-29N1CS	Sec 29 T09S R21E 0643 FSL 1901 FWL
	BHL	Sec 29 T09S R21E 0834 FSL 2152 FWL
43-047-54998	NBU 921-29N1BS	Sec 29 T09S R21E 0653 FSL 1900 FWL
	BHL	Sec 29 T09S R21E 1214 FSL 2153 FWL
43-047-54999	NBU 921-29M4BS	Sec 29 T09S R21E 0633 FSL 1902 FWL
	BHL	Sec 29 T09S R21E 0320 FSL 0782 FWL
<b>PAD NBU 921-30D</b>		
43-047-55003	NBU 921-30C1BS	Sec 30 T09S R21E 0730 FNL 0847 FWL
	BHL	Sec 30 T09S R21E 0059 FNL 2323 FWL
43-047-55004	NBU 921-30D1BS	Sec 30 T09S R21E 0707 FNL 0814 FWL
	BHL	Sec 30 T09S R21E 0210 FNL 0875 FWL
43-047-55005	NBU 921-30D1CS	Sec 30 T09S R21E 0713 FNL 0822 FWL
	BHL	Sec 30 T09S R21E 0521 FNL 0874 FWL
43-047-55006	NBU 921-30D4CS	Sec 30 T09S R21E 0724 FNL 0838 FWL
	BHL	Sec 30 T09S R21E 1190 FNL 0871 FWL
43-047-55007	NBU 921-30E1BS	Sec 30 T09S R21E 0702 FNL 0806 FWL
	BHL	Sec 30 T09S R21E 1523 FNL 0862 FWL
43-047-55008	NBU 921-30E1CS	Sec 30 T09S R21E 0719 FNL 0830 FWL
	BHL	Sec 30 T09S R21E 1872 FNL 0885 FWL

This office has no objection to permitting the wells at this time.

Michael Coulthard

Digitally signed by Michael Coulthard  
 DN: cn=Michael Coulthard, o=Bureau of Land Management,  
 ou=Division of Minerals, email=mcoulthad@blm.gov, c=US  
 Date: 2014.11.25 12:00:46 -0700

**Received: November 28, 2014**

bcc: File - Natural Buttes Unit  
Division of Oil Gas and Mining  
Central Files  
Agr. Sec. Chron  
Fluid Chron

MCoulthard:mc:11-25-14



GARY R. HERBERT  
*Governor*

SPENCER J. COX  
*Lieutenant Governor*

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
*Executive Director*

### Division of Oil, Gas and Mining

JOHN R. BAZA  
*Division Director*

## Permit To Drill

\*\*\*\*\*

**Well Name:** NBU 921-29B4CS  
**API Well Number:** 43047549630000  
**Lease Number:** UTU 0581  
**Surface Owner:** FEDERAL  
**Approval Date:** 12/17/2014

### Issued to:

KERR-MCGEE OIL & GAS ONSHORE, L.P., P.O. Box 173779, Denver, CO 80217

### Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 173-14. The expected producing formation or pool is the WASATCH-MESA VERDE Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

### Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

### Commingling:

In accordance with Board Cause No. 173-14, commingling of the production from the Wasatch formation and the Mesaverde formation in this well is allowed.

### General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

### Conditions of Approval:

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

In accordance with the Order in Cause No. 190-5(b) dated October 28, 1982, the operator shall comply with the requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operators shall ensure that the surface and or production casing is properly cemented over the entire oil

shale section as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the division.

**Notification Requirements:**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels at 801-538-5284

(please leave a voicemail message if not available)

OR

submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website

at <http://oilgas.ogm.utah.gov>

**Reporting Requirements:**

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation
- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

**Approved By:**

A handwritten signature in black ink, appearing to read "John Rogers", written over a horizontal line.

For John Rogers  
Associate Director, Oil & Gas



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

AUG 20 2014

FORM APPROVED  
OMB No. 1004-0136  
Expires July 31, 2010

## APPLICATION FOR PERMIT TO DRILL OR REENTER

5. Lease Serial No.  
UTU0581

6. If Indian, Allottee or Tribe Name

1a. Type of Work: ☒ DRILL ☐ REENTER7. If Unit or CA Agreement, Name and No.  
UTU63047A1b. Type of Well: ☐ Oil Well ☒ Gas Well ☐ Other ☐ Single Zone ☒ Multiple Zone8. Lease Name and Well No.  
NBU 921-29B4CS2. Name of Operator  
KERR-MCGEE OIL & GAS ONSHORE  
Contact: JOEL MALEFYT  
Email: JOEL.MALEFYT@ANADARKO.COM9. API Well No.  
43047349633a. Address  
P.O. BOX 173779  
DENVER, CO 80202-37793b. Phone No. (include area code)  
Ph: 720-929-6828  
Fx: 720-929-782810. Field and Pool, or Exploratory  
NATURAL BUTTES

4. Location of Well (Report location clearly and in accordance with any State requirements. \*)

At surface SWNE 1619FNL 2069FEL 40.009812 N Lat, 109.573509 W Lon

At proposed prod. zone NWNE 1227FNL 1809FEL 40.011788 N Lat, 109.572587 W Lon

11. Sec., T., R., M., or Blk. and Survey or Area  
Sec 29 T9S R21E Mer SLB14. Distance in miles and direction from nearest town or post office\*  
46.4 MILES SOUTH OF VERNAL, UT12. County or Parish  
UINTAH13. State  
UT15. Distance from proposed location to nearest property or  
lease line, ft. (Also to nearest drig. unit line, if any)  
122716. No. of Acres in Lease  
2400.00

RECEIVED

17. Spacing Unit dedicated to this well

18. Distance from proposed location to nearest well, drilling,  
completed, applied for, on this lease, ft.  
39919. Proposed Depth  
11217 MD  
11173 TVD

JAN 29 2015

20. BLM/BIA Bond No. on file  
WYB00029121. Elevations (Show whether DF, KB, RT, GL, etc.)  
4867 GL22. Approximate date of work  
01/01/2015

DIV OF OIL, GAS &amp; MINING

23. Estimated duration  
60-90 DAYS

## 24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).

4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification
6. Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature  
(Electronic Submission)Name (Printed/Typed)  
JOEL MALEFYT Ph: 720-929-6828Date  
08/14/2014Title  
REGULATORY ANALYST

Approved by (Signature)

Name (Printed/Typed)

Jerry Kenczka

Date  
JAN 26 2015Title  
Assistant Field Manager  
Lands & Mineral ResourcesOffice  
VERNAL FIELD OFFICEApplication approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

## Additional Operator Remarks (see next page)

Electronic Submission #257115 verified by the BLM Well Information System  
For KERR-MCGEE OIL & GAS ONSHORE, sent to the Vernal  
Committed to AFMSS for processing by JEANNE NEWMAN on 08/20/2014 ()

NOTICE OF APPROVAL

\*\* OPERATOR-SUBMITTED \*\* OPERATOR-SUBMITTED \*\* OPERATOR-SUBMITTED \*\*



UNITED STATES DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
VERNAL FIELD OFFICE

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



**CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL**

Company: KERR-MCGEE OIL&GAS ONSHORE  
Well No: NBU 921-29B4CS  
API No: 43-047-54963

Location: SWNE, Sec. 29, T9S, R21E  
Lease No: UTU-0581  
Agreement:

**OFFICE NUMBER: (435) 781-4400**

**OFFICE FAX NUMBER: (435) 781-3420**

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR  
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

**NOTIFICATION REQUIREMENTS**

Location Construction (Notify Environmental Scientist)	- Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify Environmental Scientist)	- Prior to moving on the drilling rig.
Spud Notice (Notify Petroleum Engineer)	- Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to running casing and cementing all casing strings to: <a href="mailto:blm_ut_vn_opreport@blm.gov">blm ut vn opreport@blm.gov</a>
BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	- Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

**SURFACE USE PROGRAM  
CONDITIONS OF APPROVAL (COAs)**

- All new and replacement internal combustion gas field engines of less than or equal to 300 design-rated horsepower must not emit more than 2 gms of NO<sub>x</sub> per horsepower-hour. This requirement does not apply to gas field engines of less than or equal to 40 design-rated horsepower.
- All and replacement internal combustion gas field engines of greater than 300 design rated horsepower must not emit more than 1.0 gms of NO<sub>x</sub> per horsepower-hour.
- If there is an active Gilsonite mining operation within 2 miles of the well location, operator shall notify the Gilsonite operator at least 48 hours prior to any blasting during construction.
- If paleontological materials are uncovered during construction, the operator is to immediately stop work and contact the Authorized Officer (AO). A determination will be made by the AO as to what mitigation may be necessary for the discovered paleontologic material before construction can continue.

**NBU 921-29G Well Pad:** NBU 921-29G1CS, NBU 921-29H4BS, NBU 921-29B4CS, NBU 921-29H1CS, NBU 921-29G1BS, NBU 921-29H1BS:

- Paleontological monitoring by a BLM permitted paleontologist is required during all ground-disturbing activities for proposed development areas found to have scientifically important fossils or in locations of high fossil potential (BLM 2012b).

Raptor management will be guided by the use of "Best Management Practices for Raptors and Their Associated Habitats in Utah" (BLM 2008 Appendix A) and "Fluid Minerals Best Management Practices" (BLM 2008 Appendix R), utilizing seasonal and spatial buffers, as well as mitigation, to maintain and enhance raptor nesting and foraging habitat, while allowing other resource uses.

- Construction and development activities will be seasonally limited for Great Horned Owls from 2/1 through 9/31, pending the results of a preconstruction nest occupancy survey (BLM 2008).
- Construction and development activities will be seasonally limited for Golden Eagle from 1/1 through 8/31, pending the results of a preconstruction nest occupancy survey (BLM 2008).
- Construction and development activities will be seasonally limited for Prairie Falcon from 4/1 through 8/31, pending the results of a preconstruction nest occupancy survey (BLM 2008).
- Raptor perch avoidance devices will be installed on all new power lines and existing lines that present a potential hazard to raptors (BLM 2008).
- Bird exclusion netting will be installed over reserve pits containing water that are left open for more than 30 days to reduce possibility of exposure to hazardous chemicals (BLM 2012b).
- KMG will install bird-excluding devices that prevent the perching and entry of migratory birds on or into its new fired vessel exhaust stacks (BLM 2012b).

**Generic COAs for all locations within the Greater Natural Buttes EIS (MAY 2012)**

- A Class III archeological survey has been conducted on all federal and/or Indian Trust lands in the GNBPA. All personnel would refrain from collecting artifacts and from disturbing any significant cultural resources in the area. KMG would be responsible for informing all persons in the area who are associated with this Project that they may be subject to prosecution for knowingly disturbing historic or archaeological sites or for collecting artifacts. All vehicular traffic, personnel movement, construction, and restoration activities would be confined to the areas examined, as referenced in the archaeological report, and to the existing roadways and/or evaluated access routes. If historic or archaeological materials were to be uncovered during construction, KMG would immediately stop surface disturbing activities that might further disturb such materials and contact the appropriate Authorized Officer (AO).
- If blasting operations are scheduled to occur within 2 miles of an active gilsonite mine, the mine operator would be notified at least 48 hours prior to blasting to coordinate activities for mine worker safety.
- KMG would conduct a paleontological survey on all of its federal locations. All personnel would refrain from collecting fossils and from disturbing any significant fossil in the GNBPA.
- An infiltration gallery will be constructed in a USFWS-approved location. An infiltration gallery is basically a pit or trench dug within a floodplain to a depth below the water table. Water is drawn from the pit rather than from the river directly. If this is not possible, KMG will limit pumping within the river to off-channel locations that do not connect to the river during high spring flows.
- If water cannot be drawn using the measures below, and the pump head will be located in the river channel where larval fish are known to occur, the following measures will apply (BLM 2012b):
- KMG will avoid pumping from low-flow or no-flow areas as these habitats tend to concentrate larval fishes;
  - KMG will avoid pumping to the greatest extent possible, during that period of the year when larval fish may be present (approximately April 1 to August 31);
  - KMG will avoid pumping, to the greatest extent possible, during the midnight hours (10:00 pm to 2:00am) as larval drift studies indicate that is a period of greatest daily activity. Dusk is the preferred pumping time as larval drift abundance is lowest.
  - KMG will screen all pump intakes with 3/32-inch mesh material..
- Damage to livestock and livestock facilities would be reported as quickly as possible to the BLM and affected livestock operators. Operators would develop and employ prevention measures to avoid damaging fences, gates, and cattleguards, including upgrading cattleguard gate widths and load-bearing requirements and fencing all open pits and cellars
- If partial or complete removal of a fence cannot be avoided, the fence would be braced and tied off per the BLM guidance. Where the fence is crossed by a road, the fence would be braced and a cattleguard and gate installed per BLM guidance.
- Speed limits would be followed and signs would be erected in lambing/calving areas, shipping pastures, or adjacent to working corrals to warn vehicle operators. (April 1 to June 1)
- In accordance with the procedures described in its Pesticide/ Herbicide Use Plan, KMG would monitor for the growth of invasive species resulting from surface disturbance caused by Project activities and would control weeds caused by Project activities.

- KMG would use its best efforts to control noxious weeds along access road authorizations, pipeline route authorizations, well sites, or other proposed facilities by spraying or mechanical removal. A list of noxious weeds would be obtained from the BLM or the appropriate County Extension Office. On BLM-administered land, a Pesticide Use Proposal would be submitted and approved prior to the application of herbicides or other pesticides or possibly hazardous chemicals.
- KMG would conduct pre-disturbance weed inventories to identify locations of noxious and invasive weed species.
- A 1- or 2-year rest period or mechanical control would be required prior to reseeding on areas treated with herbicide spraying.
- An integrated weed management plan will be developed, and include the following components:
  - Surveying for special status plant species before treating an area,
  - Considering effects to special status species when designing herbicide treatment programs,
  - Using drift reduction agents to reduce the risk of drift hazard, and
  - Using selective herbicide and a wick to backpack sprayer to minimize risks to special plants.
- Dirt ramps would be built and maintained at an angle not to exceed 45 degrees every 150 to 200 feet along open pipeline trenches to reduce habitat fragmentation and increase accessibility of small animals (mammals, reptiles, amphibians) to adjacent habitats.
- On level or gently sloping ground (5 percent slope or less), surface pipelines (4 inches or greater in diameter) would be elevated a minimum of 6 inches above the ground to allow passage of small animals beneath the pipe. This ground clearance would be achieved by placing the pipeline on blocks at intervals of 150 or 200 feet or as appropriate.
- Bird Exclusion netting will be installed over reserve pits containing water that are left open for more than 30 days to reduce possibility of exposure to hazardous chemicals.
- KMG will install bird-excluding devices that prevent the perching and entry of migratory birds on or into its new fired vessel exhaust stacks.

**DOWNHOLE PROGRAM  
CONDITIONS OF APPROVAL (COAs)**

**SITE SPECIFIC DOWNHOLE COAs:**

t9S..r21E..s29 Pad B 921-29B: nmWI NBU: #WI 921-29A1BS 921-29A1CS 921-29A4BS 921-29A4CS  
921-29B1BS 921-29B1CS 921-29B4BS  
t9S..r21E..s29 Pad C 921-29C: nmWI NBU: #WI 921-29C1BS 921-29C1CS 921-29C4BS 921-29C4CS  
921-29D1BS 921-29D1CS  
t9S..r21E..s29 Pad F 921-29F: nmWI NBU: #WI 921-29F1BS 921-29F1CS 921-29F4BS 921-29F4CS  
921-29K1BS  
t9S..r21E..s29 Pad G 921-29G: nmWI NBU: #WI 921-29B4CS 921-29G1BS 921-29G1CS 921-29H1BS  
921-29H1CS 921-29H4BS

TD\_below\_11000'

apd\_coa Downhole \_Anad(\_Kerr)

- Surface casing cement shall be brought to surface.
- Production casing cement shall be brought 200' up and into the surface casing.
- For the drilling of the surface hole section, operator is required to install an bowl diverter system or rotating head which is connected and discharges to an panic or choke bloolie line. The surface hole section of the subject well is deeper then 2,000 ft.
- Operators downhole program is for one of two TD proposals, either formation Wasatch-Mesaverde or Blackhawk. COA covering BOPE applies for well if operator drilling drilling program is 'Blackhawk Drilling Program'.

Require usage of an modified 5m stack. The 5M BOPE (minimum) shall be a modified 5m BOPE stack to include a third (3) pipe ram and one (1) remote kill line.

**All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:**

**DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS**

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.

- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.
- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well by CD (compact disc). This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

## OPERATING REQUIREMENT REMINDERS:

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at [www.ONRR.gov](http://www.ONRR.gov).
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
  - Operator name, address, and telephone number.
  - Well name and number.
  - Well location (¼¼, Sec., Twn, Rng, and P.M.).
  - Date well was placed in a producing status (date of first production for which royalty will be paid).
  - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
  - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
  - Unit agreement and/or participating area name and number, if applicable.
  - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid,



and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU 0581
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 921-29B4CS
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1619 FNL 2069 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWNE Section: 29 Township: 09.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047549630000
<b>PHONE NUMBER:</b> 720 929-6504		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: <b>11/30/2015</b>	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> <b>APD EXTENSION</b> OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:			
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:			
<input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  
 Kerr-McGee Oil & Gas Onshore, L.P. (Kerr-McGee) respectfully requests an extension to this APD for the maximum time allowed. Please contact the undersigned with any questions and/or comments. Thank you.

Approved by the  
 December 07, 2015  
 Oil, Gas and Mining

Date: \_\_\_\_\_

By:

<b>NAME (PLEASE PRINT)</b> Jennifer Thomas	<b>PHONE NUMBER</b> 720 929-6808	<b>TITLE</b> Regulatory Specialist
<b>SIGNATURE</b> N/A	<b>DATE</b> 11/30/2015	



**The Utah Division of Oil, Gas, and Mining**

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

**Request for Permit Extension Validation Well Number 43047549630000**

API: 43047549630000

Well Name: NBU 921-29B4CS

Location: 1619 FNL 2069 FEL QTR SWNE SEC 29 TWNP 090S RNG 210E MER S

Company Permit Issued to: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date Original Permit Issued: 12/17/2014

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☒ Yes ☐ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Signature: Jennifer Thomas

Date: 11/30/2015

Title: Regulatory Specialist Representing: KERR-MCGEE OIL & GAS ONSHORE, L.P.

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU 0581
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 921-29B4CS
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1619 FNL 2069 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWNE Section: 29 Township: 09.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047549630000
<b>PHONE NUMBER:</b> 720 929-6454		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 11/3/2016  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE   <input type="checkbox"/> CHANGE TO PREVIOUS PLANS   <input type="checkbox"/> CHANGE WELL STATUS   <input type="checkbox"/> DEEPEN   <input type="checkbox"/> OPERATOR CHANGE   <input type="checkbox"/> PRODUCTION START OR RESUME   <input type="checkbox"/> REPERFORATE CURRENT FORMATION   <input type="checkbox"/> TUBING REPAIR   <input type="checkbox"/> WATER SHUTOFF   <input type="checkbox"/> WILDCAT WELL DETERMINATION         </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING   <input type="checkbox"/> CHANGE TUBING   <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS   <input type="checkbox"/> FRACTURE TREAT   <input type="checkbox"/> PLUG AND ABANDON   <input type="checkbox"/> RECLAMATION OF WELL SITE   <input type="checkbox"/> SIDETRACK TO REPAIR WELL   <input type="checkbox"/> VENT OR FLARE   <input type="checkbox"/> SI TA STATUS EXTENSION   <input type="checkbox"/> OTHER         </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR   <input type="checkbox"/> CHANGE WELL NAME   <input type="checkbox"/> CONVERT WELL TYPE   <input type="checkbox"/> NEW CONSTRUCTION   <input type="checkbox"/> PLUG BACK   <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION   <input type="checkbox"/> TEMPORARY ABANDON   <input type="checkbox"/> WATER DISPOSAL   <input checked="" type="checkbox"/> APD EXTENSION           OTHER: <input style="width: 100%;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Kerr-McGee Oil & Gas Onshore, L.P. (Kerr-McGee) respectfully requests an extension to this APD for the maximum time allowed. Please contact the undersigned with any questions and/or comments. Thank you.		
<div style="color: red; font-weight: bold;">             Approved by the              November 08, 2016              Oil, Gas and Mining           </div> <div style="color: red; font-weight: bold;">             Date: _____              By:  </div>		
<b>NAME (PLEASE PRINT)</b> Joel Malefy	<b>PHONE NUMBER</b> 720 929-6828	<b>TITLE</b> Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 11/3/2016	



**The Utah Division of Oil, Gas, and Mining**

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

**Request for Permit Extension Validation Well Number 43047549630000**

API: 43047549630000

Well Name: NBU 921-29B4CS

Location: 1619 FNL 2069 FEL QTR SWNE SEC 29 TWNP 090S RNG 210E MER S

Company Permit Issued to: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date Original Permit Issued: 12/17/2014

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☒ Yes ☐ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Signature: Joel Malefyt

Date: 11/3/2016

Title: Regulatory Analyst Representing: KERR-MCGEE OIL & GAS ONSHORE, L.P.